

BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2013-14/RD/WORK_INDENT9101/CALL-6


APPROVED SCHEDULE - B

No.EE/BTP/BBMP/E-PMT/04/2014-15, Date:17.06.2014

Improvements to Roads and Drains at Bhagyasree layout Near Chamundeshwari Temple in Ward No.06 Byatarayanapura Sub Division

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of	
				R NATARAJ	
				In Figures	In Words
1	234.6	KSRRB 300-2. Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications complete as per specifications MORTH chapter 3. Page No. 152 / Item No. 19.2 / PWD SR 2013-14	Cum	90.0	Rupees Ninety Only
2	81.41	KSRB 4-1.3 : Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @ 180 Kgs using 40mm and down size graded granite metal, coarse aggregates @ 0.85 cum and fine aggregates @ 0.58cum machine mixed, concrete laid in layers not exceeding 15 cms thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.2 Page No. 12 /Item No. 4.3 PWD SR - 2013-14	Cum	4290.0	Rupees Four Thousand Two Hundred Ninety Only
3	7.02	KSRB 5.2-2 : Providing and constructing granite / trap / basalt size stone masonry in foundation with cement mortar 1:6, stone hammered dressed in courses not less than 20 cms high, bond stones, at two m. apart in each course including cost of materials, labour, curing complete as per specifications. KBS 5.1.13 PWD SR 2013-14 (P. 25 / I. 5.6)	Cum	3484.0	Rupees Three Thousand Four Hundred Eighty Four Only
4	11.7	KSRB 15.1.3: Providing ruled pointing to coursed stone masonry with cement mortar 1:3, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing complete as per specifications. Page No. 122 / Item No. 15.3 / PWD SR 2013-14	Sqm	76.0	Rupees Seventy Six Only
5	0.78	KSRB 4-1.6 : Providing and laying in position plain cement concrete of mix M15 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing complete as per specifications, specification. No. KBS 4.1,4.2. No. 12 / Item No. 4.6 / PWD SR 2013-14	Cum	4690.0	Rupees Four Thousand Six Hundred Ninety Only

6	273.9	KSRB 4-6.4: Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour complete as per specifications. Specification No. KBS 4.6.2 Page No.17 / Item No. 4.31 PWD SR - 2013-14	Sqm	271.0	Rupees Two Hundred Seventy One Only
7	58.05	KSRB 4.2.2 : Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 Kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878cum and fine aggregates @ 0.459 cum with superplasticiser @ 3lts confirming to IS 9103-1999 reaffirmed-2008, machine mixed, concrete laid in layers not exceeding 15 cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, return walls, wall (any thickness) including attached plasters, columns, piers, abutments, pillars, posts, struts, buttresses, including cost of all materials, labour, HOM of machinery, curing complete as per specifications. Specification No. KBS 4.1, 4.6 Page No. 13 / Item No. 4.11 PWD SR - 2013-14	Cum	5639.0	Rupees Five Thousand Six Hundred Thirty Nine Only
8	40.64	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. Specification No. KBS 4.6.3 Page No. 19 / Item No. 4.46.2 PWD SR 2013-14 TMT bar Fe 500	Qtl	7450.0	Rupees Seven Thousand Four Hundred Fifty Only
9	130.5	KSRB M300-53: Construction of embankment with approved material gravel/murum with all lifts and leads, transporting to site, spreading, grading to required slope and compacting to meet requirement table 300-2 complete as per specifications. (which includes cost of gravel/murum, watering charges & compaction by vibratory roller) MORTH specification No. 305, No. 159 / Item No. 19.60 / PWD SR 2013-14	Cum	163.0	Rupees One Hundred Sixty Three Only
10	174	Providing, laying, spreading and compacting graded stone aggregate to wet mix macadam specification including premixing the Material with water at OMC in mechanical mix plant carriage of mixed Material by tipper to site, laying in uniform layers with paver in sub-base / base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications (P. 170 / I. 20.18) PWD SR - 2013-14.	Cum	1121.0	Rupees One Thousand One Hundred Twenty One Only
11	870	KSRB 500-1.1 : Cleaning the existing WBM road surface including removing of binding materials and other foreign matter with wire bushes and small picks, sweeping with brooms or soft brushes and finally dusting with old gunny bags and / or compressed air to receive bituminous treatment including cost of all materials, labour, HOM of machineries, curing complete as per specifications. Specification No. 500-1.3 (P.175 / I.21.1) PWDSR 2013-14	Sqm	10.0	Rupees Ten Only



12	870	KSRRB 500-5: providing and applying primer coat from 12.2 to 14.6kg per 10 sqm for surfaces of high porosity over prepared surface of granular base with cut back M.C.-70 or any other bitumen mixed with diesel at 13 kg per 10 sqm heated in bitumen boiler fitted with spray set (excluding cleaning of road surface) including cost of all materials, labour, HOM of machineries complete as per specifications. MORTH chapter 5, No. 175 / Item No. 21.5 / PWD SR 2013-14	Sqm	142.0	Rupees One Hundred Forty Two Only
13	21.75	KSRRB M500-18: Providing and laying semi dense bituminous concrete 25mm thick with 100-120 TPH batch type HMP producing an average output of 75 tonnes per hour using crushed aggregates of specified grading, premixed with bituminous binder at 4.5 to 5% of mix and filler, transporting the hot mix to work site, laying with a hydrostatic paver finisher with sensor control to the required grade, level and alignment, rolling with smooth wheeled, vibratory and tandem roller to achieve the desired compaction as per MORTH specifications clause No. 500.8 complete in all respects as per specifications With 60/70 grade bitumen using 40-60 HMP, No. 178 / Item No. 21.20.4 / PWD SR 2013-14.	Cum	9981.0	Rupees Nine Thousand Nine Hundred Eighty One Only
14	39.6	Providing and laying cement concrete using 20mm and down size granite jelly of ready mixed concrete (RMC) for R.C.C works laid in 15cms thick layers and well compacted vibrating, curing, finishing with necessary cement mortar, form works and scaffoldings to withstand pumping of concrete, with all lead and lifts etc., complete (exclusive of cost of steel and fabrication charges.) Ready mixed Cement concrete M-20 (1:1.5:3) for raft foundation, column footing, main and secondary beams. Page No. 19 / Item No. 4.48.1/ PWD SR 2013-14	Cum	6464.0	Rupees Six Thousand Four Hundred Sixty Four Only
15	396	Vaccum De-watering with vaccum pump and suction mat and compaction with skin floater clubbed with floating disc including cost of generator HOM of machinery Screed Vibratory, Power Floater, blade and disc etc., with all lead and lift No. 190 / Item No. 22.7/ PWD SR 2013-14	Sqm	90.41	Rupees Ninety and Forty One Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92